

PERENNIALS:						
QTY	KEY	BOTANICAL NAME	COMMON NAME	SIZE	ROOT	SPACING
2	AR	<i>Acer rubrum</i>	Red Maple	2" Cal.	B&B	as shown
18	AA	<i>Amelanchier arborea</i>	Downy serviceberry	3-4' HT.	B&B	as shown
18	HV	<i>Hamelis virginiana</i>	American Witchhazel	2-3' HT.	CONT.	as shown
7	VB	<i>Viburnum dentatum</i>	Arrowwood Viburnum	2-3' HT.	CONT.	as shown
59	CA	<i>Clethra alnifolia</i>	Summersweet	18-24' HT.	CONT.	3' O.C.
50	DP	<i>Dennstaedtia punctilobula</i>	Hay Scented Fern	1 GAL.	CONT.	18" O.C.
50	AD	<i>Aster divaricus</i>	White wood Aster	1 GAL.	CONT.	18" O.C.
19	IG	<i>Ilex glabra</i>	Inkberry	18"- 24" HT	CONT.	as shown
12	VA	<i>Vaccinium Angustifolium</i>	Low bush Blueberry	1 GAL.	CONT.	as shown
12	RV	<i>Rhododendron viscosum</i>	Swamp Azalea	18-24' HT.	CONT.	as shown

NOTES:
 1. ALL NEW PLANTING MATERIAL SHALL CONFORM TO MINIMUM GUIDELINES ESTABLISHED BY THE AMERICAN STANDARD FOR NURSERY STOCK PUBLISHED BY THE AMERICAN NURSESMEN AND LANDSCAPE ASSOCIATION (ANLA). ALL NEW PLANT MATERIAL FOR THE PROJECT SHALL BE OF SPECIMEN QUALITY AND PLANT HEIGHT MEASURED FROM ROOT FLARE NOT BOTTOM OF POT OR BURLAP BALL.
 2. CONTRACTOR TO DISCUSS AND REVIEW SLOPED PLANTING CONDITIONS FOR ALL TREES AND LARGER PLANT MATERIAL WITH LANDSCAPE ARCHITECT PRIOR TO PLACEMENT

LEGEND

- PROPERTY LINE
- - - ZONING SETBACK
- L.O.W. LIMIT OF WORK/HEAVY CONSTRUCTION EXISTING CONTOUR
- 50 PROPOSED CONTOUR
- EXISTING DECIDUOUS TREE TO REMAIN
- ⊙ EXISTING EVERGREEN TREE TO REMAIN
- PROPOSED DECIDUOUS TREE
- 1 Pj quantity TREE TAG
- 1 Pj species symbol
- 1 Pj quantity SHRUB TAG
- 1 Pj species symbol
- 1 Pj quantity PERENNIAL TAG
- 1 Pj species symbol
- ▨ PERENNIAL HATCH

GENERAL NOTES:

NORTH

FOR PERMITTING ONLY
NOT FOR CONSTRUCTION

GREGORY LOMBARDI DESIGN, INC.
 Landscape Architecture
 2235 Massachusetts Avenue
 Cambridge, Massachusetts 02140
 Phone 617.492.2808 Fax 617.492.2904

No.	Date	Comment

Date: 9 SEPTEMBER 2020 Scale:
 Project No.: 19032 Drawing by: HB/JS Checked by: RW/GL

CONSERVATION PLANTING PLAN

