


S 44-09-11 E
100.55'

N 90-00-00 E
386.00'

S 02-18-24 E
173.88'

N 74-52-55 W
743.63'



DISTANCE DATA:		To	To
From	Cor	"A"	"B"
MH Sing (#1)	25'4"	47'	47'
MH Sing (#2)	26'6"	51'3"	51'3"
MH Sing (#3)	28'	54'	54'
Pump Tank (#4)	29'	58'	58'
Pump Tank (#5)	33'9"	60'3"	60'3"
SAS(#6)	26'3"	43'6"	43'6"
SAS(#7)	57'	24'3"	24'3"
SAS(#8)	49'3"	57'	57'
SAS(#9)	71'	45'3"	45'3"
Insp. Port (IP)	38'	47'6"	47'6"

GRADE DATA:	Proposed	As-built
House Out	56.6	59.7
Tank In	56.0	57.3
Tank Out	55.7	57.0
Pump In	55.6	56.8
Pump Out	55.3	57.1
Manifold Inv.	56.6	56.6
Lateral Inv.	57.1	57.1

SAS - 24'x56' (OA) pressure field
4" building sewer line
2" pump discharge line
2" manifold
1.5" laterals
All piping is sched. 40 PVC

SITE PLAN
1" = 20'

As-built Septic Plan
27R Pioneer Road
Hingham, Massachusetts
1/26/2011

MCS McSweeney Associates
150 Union St. Hingham (781) 749-2859
745 Winter St. Hanson (781) 826-4571

